

PREFABRICATED/MANUFACTURED FIREPLACE INSTALLATION

- ☞ H.V.A.C. permit is required. (Available in the Cudahy Inspection Department)
- ☞ Unit purchased must be tested and listed by a recognized testing laboratory such as U.L. (Underwriters Laboratories) or Warnock Hersey.
- ☞ Unit must be installed in strict accordance with manufacturer's installation instructions.
- ☞ Unit or any accessory parts cannot be altered in any way, as this action voids listing.
- ☞ Any electrical work done in conjunction with this project requires a separate permit. The electrical permit may only be obtained by a contractor who is licensed by the City of Cudahy.
- ☞ The same chimney cannot be used to vent products of combustion of dissimilar fuels simultaneously. (The same chimney cannot be used when burning wood and gas or oil etc.)

- ☞ Inspections required are: in rough stage to check construction, proper clearances to combustibles, firestopping, chimney height, and generally to compare installation to manufacturer's installation instructions.
- ☞ Final inspection upon completion.

NOTE: Please phone 48 hours in advance to schedule an inspection.

This informational sheet is not intended to answer commonly asked questions. Proper installation and construction is the responsibility of the owner or his designated agent. **IF YOU HAVE ANY OTHER QUESTIONS PLEASE ASK US.** (414-769-2211)